



Scope of Work & Pricing

to be performed by Greystone Construction

Furnish & Install Budget Price:

- Replacement Cover for 45'x50' Fabric Building
- 12.5 ounce, 23 mil polyethylene Non-FR fabric
 - Single piece cover design
- Two Replacement Endwall Fabric Panels
- Two Fabric Door Panels
- Reuse all original tension tubes
- Existing steel to remain
- Existing Cables and purlins to remain
- Pull covers and tension the fabric to industry specification
- Furnish and Install new straps and PVC
- Furnish and Install new 2" winches and straps
- Freight to Lodi, WI included
- 5.5% Sales tax on materials included
- Provide all necessary labor and equipment to complete items noted above
- Pricing valid for 15 days

Furnish & Install Budget Price: \$32,830

Alternate/Add:

- Add a man door to front endwall
 - Includes 3' wide man door and framing

Furnish & Install Budget Price Add: \$2,500

Exclusions – Items not included, but may apply to overall project:

- Architectural and Civil Engineering
- Permits & Fees
- Prevailing wage rates
- Dumpsters
- Testing & special inspections by owner – Soil borings, soils testing, concrete testing, bolt inspection, etc
- Site work including, but not limited to: site prep, import or export of materials, etc
- Assumed building has 20' clear on all four sides for staging/erection and building engineering requirements
- Site specific safety requirements
- All electrical & mechanical systems
- All winter conditions
- Dumpster/Disposal of removed cover
- Greystone Construction is not liable and will not accept any responsibility for the structural design and structural performance of this existing building to be recovered.